

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 179-20911-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Burich Exploration Inc. OPERATORS LICENSE NO. 7448
ADDRESS 11225 Edinborough Way Parker, Colo. 80134 PHONE # (303) 841-9417
LEASE (FARM) SIMON WELL NO. 1 WELL LOCATION NW1/4NW1/4 COUNTY Sheridan
SEC. 20 TWP. 9S RGE 26 (E) or (W) TOTAL DEPTH 4010 PLUG BACK TO Surface

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 322 CEMENTED WITH 225 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run Drill pipe to 2300'. Pump to BBHs. H2O
spacer. Mix 25 SKS. 6 1/4" FOZ mix 6' to gel. Run 3' BBH spacer. Displace w/ mud
BALANCE. Pull Drill pipe to 1450. 10. BBHs. H2O spacer. Mix 100 SKS 6 1/4" FOZ mix 6' to
(If additional space is needed use back of form) over

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-16-1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Melvin K. Taylor, Inc. PHONE # (308) 345-3214

ADDRESS 802 E 6th McCook, NE. 69001

PLUGGING CONTRACTOR Golden Eagle Drilling Inc. LICENSE NO. 8682

ADDRESS P.O. Box 983 McCook, NE. 69001 PHONE # (308) 345-3214

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: J. David Burch
(Operator or Agent)

RECEIVED
MAR 11 1988
03-11-1988
CONSERVATION DIVISION
Wichita, Kansas

DATE: 1-20-1988

gel. w/ 1 SK of High Seal. 3 1/2 BBL of Mud BALANCE. Pull Drill Pipe to
375'. MIX 40 SKs. 60/40 Poz MIX 6% gel. Push Plug to 40'. Fill to SURFACE.
plug Mousehole + RAT Hole w/ LAST 35 SKs. Fill to SURFACE.
JOB COMPLETE.