

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179,20-852-0000

LEASE NAME Minium

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 32 TWP. 9 RGE. 26 (E) or (W)

COUNTY Sheridan

Date Well Completed 12/2/85

Plugging Commenced 11/25/97

Plugging Completed 11/25/97

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE# (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/25/97 (date)

by Herb Deines - witnessed by Mr. Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lansing-Kansas City Depth to Top 3848' Bottom 4077' T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	259'	none
				5 1/2"	4097'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pump 300 sx 60/40 pozmix (10% gel, 500# hulls) cement down 5 1/2" casing, pressure up to 500#, shut in @ 200#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. NA

Address P. O. Box 31 Russell, KS 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1997



Vickie Cole
Vickie Cole Notary Public

My Commission Expires: 10-18-2000