

15-179-20385-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Sheridan County, Sec. 35 Twp. 9 Rge. 26W (E) (W)

Location as "NE/CNW/SW" or footage from lines C E/2 SE SE

Lease Owner Chief Drilling Co., Inc.

Lease Name Fore, et al Well No. 1

Office Address 905 Century Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 19, 1974 19

Application for plugging filed May 18, 1974 19

Application for plugging approved May 18, 1974 19

Plugging commenced May 19, 1974 19

Plugging completed May 19, 1974 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well 4080' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	214'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1250' w/70 sacks cement.
Plugged through drill pipe @ 225' w/30 sacks cement.
Plugged through drill pipe @ 40' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1974
05-23-1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson

905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of May, 1974



Virginia S. Fabian
Notary Public.

15-179-20385-00-00

WELL LOG

CHIEF DRILLING CO., INC. &
P-S PETROLEUM CO.
Suite 905 Century Plaza
Wichita, Kansas 67202

#1 FORE, etal ^{KCC} ~~ZAP~~
C E/2 SE SE Sec. 35-9-26W
Sheridan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 208' of 8 5/8" w/150
sacks common quick set
cement

COMMENCED: 5/11/74
COMPLETED: 5/19/74

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Hole	0	658	2572 Gr.
Shale	658	1555	2574 D.F.
Shale & Shells	1555	1800	2577 K.B.
Sand	1800	1970	
Shale & Shells	1970	2194	
Anhydrite	2194	2228	
Shale & Shells	2228	2874	
Shale & Lime	2874	3375	
Lime & Shale	3375	4080	
Total Depth	4080		

FORMATION TOPS

Anhydrite	2194+ 383
Base Anhy.	2228+ 349
Heebner	3798-1221
Toronto	3819-1242
Lansing	3833-1256
B.K.C.	4067-1490
R.T.D.	4080-1503

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C E/2 SE SE Sec. 35-9-26W, Sheridan County, Kansas to the best of my knowledge and belief.

STATE CORPORATION COMMISSION

CHIEF DRILLING CO., INC.

MAY 23 1974
05-23-1974
CONSERVATION DIVISION
Wichita, Kansas

Jim Robinson
Jim Robinson, Vice President

Subscribed and sworn to before me this 22nd day of May, 1974.

Virginia S. Fabian
Virginia S. Fabian, Notary Public

