

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sheridan County, Sec. 36 Twp. 9 Rge. 26 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NW SE

Lease Owner Theodore Gore

Lease Name D. Inloes Well No. 1

Office Address 650 Fourth National Bank Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 25, 1959 19

Application for plugging filed September 24, 1959 19

Application for plugging approved September 24, 1959 19

Plugging commenced September 24, 1959 19

Plugging completed September 24, 1959 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4110 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	224	8 5/8"	209'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set at 550' w/20 sx cement  
Plug set at 200' w/20 sx cement  
Plug set at 40' w/10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.


Dan J. Kornfeld (employee of owner) ~~XXXXXXXXXXXXXXXXXX~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

650 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1959



Lucille H. Harr  
Notary Public.

My commission expires October 21, 1962

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1959  
10-03-1959  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-00148-00-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1959  
10-13-1959  
CONSERVATION DIVISION  
Wichita, Kansas

LOG

COMPANY: Theodore Gore

CONTRACTOR: Empire Drilling Company

FARM: D. Inloes # 1

LOCATION: NE NW SE of Section 36-9-26W, Sheridan County, Kansas

COMMENCED: September 16, 1959

COMPLETED: September 25, 1959

ELEVATION: 2605 KB

POTENTIAL: D & A

\*\*\*\*\*

0	to	224	Surface
224	to	2241	Shale-Shells
2241	to	2276	Anhydrite
2276	to	2895	Shale-Shells
2895	to	3298	Shale-Lime
3298	to	3380	Lime-Shale
3380	to	3495	Shale-Lime
3495	to	3850	Lime-Shale
3850	to	4075	Lime
4075	to	4110	Lime-Shale
4110			Rotary Total Depth

SET 209° 8 5/8" w/150 sx cement


ELECTRIC LOG TOPS:

Heebner	3827	-1222
Toronto	3850	-1245
Lansing	3868	-1263
Base Kansas City	4097	-1492
Schlumberger TD	4108	

\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the D. Inloes # 1, NE NW SE of Section 36-9-26W, Sheridan County, Kansas, as reflected by the files of Empire Drilling Company.

  
 Dan J. Kornfeld



SUBSCRIBED AND SWORN to before me, a notary public within and for Sedgwick County, Kansas, this 30th day of September, 1959.

  
 Lucille H. Harr

My Commission expires October 21, 1962.