


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-173-20366-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 1 Twp. 9 Rge. 27W(E) (W)
Location as "NE/CNW4SW4" or footage from lines SW SW NE
Lease Owner Chief Drilling Co., Inc.
Lease Name Popp Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/22/73 19.
Application for plugging filed 9/21/73 19.
Application for plugging approved 9/22/73 19.
Plugging commenced 9/22/73 19.
Plugging completed 9/22/73 19.
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Depth to top Bottom Total Depth of Well 4030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	219'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 1375' w/70 sacks cement.
Plugged through drill pipe @ 245' w/20 sacks cement.
Plugged through drill pipe @ 40' w/10 sacks cement.


RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1973
09-28-1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1973



My commission expires August 5, 1975

Virginia S. Fabian
Notary Public.

WELL LOG

15-179-20366-00-00

CHIEF DRILLING CO., INC.
Suite 905 Century Plaza
Wichita, Kansas 67202

POPP #1
SW SW NE Sec. 1-9-27W
Sheridan County, Kansas

CONTRACTOR: Company tools
CASING RECORD: Set 206' of 8 5/8" w/150
sacks common quick set cement

COMMENCED: 9/15/73
COMPLETED: 9/22/73

FORMATION	FROM	TO
Surface Sand & Gravel	0	222
Blue Shale & Sand	222	280
Shale & Sand	280	1575
Shale & Shells	1575	1880
Sand	1880	2051
Shale & Shells	2051	2276
Anhydrite	2276	2312
Shale & Shells - Red Bed	2312	2400
Shale & Lime	2400	2700
Shale & Shells	2700	2843
Shale w/Lime Streaks	2843	3060
Shale & Lime	3060	3815
Lime & Shale	3815	3900
Lime	3900	4030
Total Depth	4030	

ELEVATION

2666 Gr.
2668 D.F.
2671 K.B.

FORMATION TOPS

Anhydrite 2276+ 395
Base Anhy. 2312+ 359
Heebner 3782-1111
Toronto 3803-1132
Top Lansing 3820-1149
Est. B.K.C. 4043-1372
R.T.D. 4030-1359

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1973
09-28-1973
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SW NE of Section 1-9-27W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson

Jim Robinson, Office Manager

Subscribed and sworn to before me this 27th day of September, 1973.

Virginia S. Fabian

Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:

August 5, 1975

