

15-179-20576-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County, Sec. 5 Twp. 9S Rge. 27W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW NW SW


Lease Owner J. A. Allison
Lease Name Kennedy Well No. #1
Office Address 300 W. Douglas, Suite 305, Wichita, Kans. 202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole

Date Well completed January 24, 1981
Application for plugging filed January 24, 1981
Application for plugging approved January 24, 1981
Plugging commenced January 24, 1981
Plugging completed January 24, 1981
Reason for abandonment of well or producing formation
dry hole

If a producing well is abandoned, date of last production
N/A 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4050'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	244'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

1260' 70 SX
170' 20 SX
40' 10 SX
RH 5 SX

50 - 50 PAZ 6% gel

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Service Company

RECEIVED
02-02-1981
STATE CORPORATION COMMISSION
FEB. 2 1981
CONSERVATION DIVISION
WICHITA, KANSAS


STATE OF Kansas COUNTY OF Sedgwick
Paul A. Seymour, III (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above described well
as filed and that the same are true and correct. So help me God.

(Signature) Paul A. Seymour III
Paul A. Seymour, III, Box 8287-Munger Station
(Address) Wichita, Ks. 67208

SUBSCRIBED AND SWORN TO before me this 30th day of January, 19 81

LaDonna F. Landrum
LaDonna F. Landrum Notary Public.

My commission expires August 18, 9184



15-179-20576-00-00

BIG SPRINGS DRILLING, INC.

P.O. BOX 8287
MUNGER STATION
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

January 30, 1981

Drillers Log

Re: Kennedy #1
SW NW SW
Sec. 5 Twp 9S Rg 27W
Sheridan County, Kansas

OPERATOR: J. A. Allison
CONTRACTOR: Big Springs Drilling, Inc.
COMMENCED: January 15, 1981
COMPLETED: Janusry 24, 1981

Surface Pipe: 244' of 8 5/5" w/200 SX Common 2% gel 3% ccl

0	990	Clay, Shale & Sand
990	1421	Shale
1421	2281	Shale & Sand
2281	2316	Anhydrite
2316	2953	Shale
2953	3193	Shale & Shells
3193	3317	Shale
3317	3520	Shale & Lime
3520	3621	Shale
3621	4050	Lime & Shale
4050		RTD

RECEIVED
FEB - 2 1981
02-02-1981
CONSERVATION DIVISION
Wichita, Kansas

We certify that the above and foregoing is a true and correct copy of the log on the Kennedy #1 located in Sheridan County, Kansas.

Big Springs Drilling, Inc.

Paul A. Seymour III
Paul A. Seymour, III

Subscribed and sworn to before me this 30th day of January, 1981.

LaDonna F. Landrum
LaDonna F. Landrum Notary Public

My Commission Expires:

August 18, 1984

