

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-179-20575-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County, Sec. 8 Twp. 9S Rge. 27 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
N/2 SW/4 SE/4

Lease Owner Rains & Williamson Oil Co., Inc.
Lease Name Niermeier A #1 Well No. #1
Office Address 435 Page Court, 220 W. Douglas, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 12-4-80 19
Application for plugging filed 12-4-80 19
Application for plugging approved 12-4-80 19
Plugging commenced 12-4-80 19
Plugging completed 12-4-80 19


Reason for abandonment of well or producing formation
Commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4087'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	340'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 1320' w/60 sx.
Plug @ 240' w/30 sx.
Plug @ 40' w/10 sx.
Rat Hole 5 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of January, 1981



Juanita M. Green Notary Public.

10-4-83

RECEIVED
STATE CORPORATION COMMISSION
01-13-1981
JAN 13 1981
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

15-179-20575-00-00

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 8 T. 9S R. 27W

LOC. N/2 SW SE

WELL NAME: Niermeier #1

COUNTY: Sheridan

RIG NO. #4

TOTAL DEPTH 4087'

ELEVATION 2703 GL 2708 KB

COMMENCED: 11-25-80

COMPLETED: 12-4-80

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 340' w/225 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Clay, Sand & Shale	230
Shale	1300
Sand & Shale	1439
Shale	2650
Shale & Lime	2890
Shale & Sand	3136
Shale	3320
Shale & Lime	3400
Shale	3505
Lime & Shale	3695
Shale & Lime	3790
Lime & Shale	3900
Shale	3995
Lime	4087
<u>ROTARY TOTAL DEPTH</u>	<u>4087</u>

RECEIVED
STATE CORPORATION COMMISSION

JAN 13 1981
01-13-1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)


SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Niermeier #1 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 10 day of January, 1981.

My Appointment Expires:

10-4-83

Juanita M. Green
Juanita M. Green