

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03222-00-00

Spot: ~~SWS12W~~ SESWNW Sec/Twnshp/Rge: 1-16S-12W

2966 ~~2970~~ feet from S Section Line, ~~3630~~ feet from E Section Line

Lease Name: SCHAUF C

3968 Well #: 5

County: BARTON

Total Vertical Depth: 3322 feet

Operator License No.: 5259

Op Name: MAI OIL OPERATIONS, INC.

Address: 4514 COLE AVE STE 740 LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3314	0	w/125 sxs cmt
SURF	8.625	295	0	w/175 sxs cmt

\$ 107.97

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/23/2007 10:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOM

Company: MAI OIL OPERATIONS, INC.

Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: BRUCE BASYE

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/23/2007 1:30 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 2800' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Pulled to 1800' - pumped 100 sxs cement with 300# hulls.
Pulled to 400' - circulated with 50 sxs cement with 200# hulls.
POOH. Tied onto casing - circulated backside with 30 sxs cement.

INVOICED

DATE 9-17-07
INV. NO. 2008060397

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 06 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed

Case Morris


(TECHNICIAN)

Form CP-2/3

AUG 27 2007

PKT

3-221 MAP NO. SEC 1-16S-12W
 STATE Kans. COUNTY Barton LOC. SW SE NW
 OPER Kaiser-Francis, Tulsa, Okla. FT. PR. LINE
 WELL #5 FARM "Schauf "C" FT. PR. LINE
 POOL Kraft-Prusa ELEV. 1876 GR. 1878 OF 1891 KB
 CONT H-30 Tools GEOL.
 CO 3350' Arb Test
 INT 1/24/64 SPUD 1/24/64 COMP 3/24/64



ID 3319 FM Arb PSTD
 PRODUCING FM. FROM TO W/PERF TREATMENT
 Arb 3314-19 OH Natural

P State Pot: Pump 48 BOPD, NW, Grav. 41 deg.
 8-5/8" @ 295 w/175 sx.
 5 1/2" @ 3314 w/125 sx.

Data Inc.

KB Spl Tops:							
Anh	743	+1148	Tor	2951	-1060	BKc	3244 -1353
B/Anh	775	+1116	Dg	2964	-1073	Arb	3314 -1423
Top	2650	- 759	BL	3025	-1134	RTD	3319 -1428
Hb	2933	-1042	Lans	3038	-1147		

DST #1 (Top) 2849-90, Op 1 hr., GTS/5", R 120' GCM + 60' GCM&OCM