

KCC Per GPS +
Dist. 4

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23237-00-00

Spot: ~~SESESW~~ SWSESW Sec/Twnshp/Rge: 16-10S-22W

467 ~~500~~ feet from S Section Line, ~~2070~~ feet from W Section Line

Lease Name: HERMAN FARMS 3418 Well #: 16-1

County: GRAHAM

Total Vertical Depth: 4008 feet

Operator License No.: 33813

Op Name: JASON OIL COMPANY, LLC

Address: 3718-183RD ST. PO BOX 701
RUSSELL, KS 67665

String Size Depth (ft) Pulled (ft) Comments

PROD 5.5 3920

SURF 8.625 219

\$130.26

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/11/2007 9:00 AM

Plug Co. License No.: 32528

Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES

Proposal Rcvd. from: DAVID FUNK

Company: JASON OIL COMPANY, LLC

Phone: (785) 324-1041

Proposed
Plugging
Method:

Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/12/2007 7:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perf casing at 1850' with knife pumped and 80 sxs cement with 200# hulls.
Displaced to 1500' - cut casing at 1130'.
Pulled up to 1050' - pumped 100 sxs cement with 200# hulls.
Pulled casing to 160' - pumped 120 sxs cement - good circulation of cement.
Pulled rest of the casing - hole stand full of cement.

Perfs:

Top	Bot	Thru	Comments
3692	3696		
3647	3650		
3595	3601		

INVOICED

DATE 9-20-07

INV. NO. 2008060436

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN RECEIVED)
KANSAS CORPORATION COMMISSION

SEP 14 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

SEP 13 2007

PRET