

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20162-00-01 *o2 KCC afz*
Spot: NWNWSE Sec/Twnshp/Rge: 12-5S-22W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: NELSON C Well #: 3
County: NORTON Total Vertical Depth: 3469 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

CIBP Size: feet: 3450
PROD Size: 4.5 feet: 3465 125 SX CMT
SURF Size: 8.625 feet: 255 210 SX CMT

\$112⁷⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2004 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Squeezed 750' w/50 sxs; 490' w/200 sxs.
Ran 2 3/8" sealtite to 3200' - cemented with 150 sxs cwc. (Daystar).
Gore Oil purchased - decided to P/A.
Ordered out 100 sxs Acon II cement.
Perf Tech perforated four holes at 2800' and four holes at 3250'.
Took injection rate - one bpm 900#.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2004 10:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Acid Services hooked up to 2 3/8" sealtite and pumped 27 sxs Acon II cement.
Max. P.S.I. 1500#. S.I.P. 500#.
Hooked up to 8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside - 2 3/8" tubing - pumped 5 sxs cement.
Max. P.S.I. 1100#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3343	3345		
750			
490			
390			
255			

RECEIVED
NOV 03 2004
KCC WICHITA

Remarks: ACID SERVICES, INC.-PRATT.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 11-3-04

INV. NO. 2005060744

Form CP-2/3

NOV 02 2004

IMAGED

R P NIXON OPERATIONS
 207 W 12TH ST #3 NELSON "C" 12-5-22W
 HAYS, KS 67601 NW NW SE
 CONTR ABERCROMBIE DRILLING CTY NORTON
 GEOL _____ FIELD DENSMORE
 E 2051 KB CM 1/15/80 CARD ISSUED 4/24/80 IP P 20 BOPD, NO WTR
 REAG OH 3465-3469
 API 15-137-20,162

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1650	+ 401
B ANH		1671	+ 380
HEEB		3179	-1128
TOR		3209	-1158
LKC		3223	-1172
B KC		3407	-1356
REAG		3464	-1413
RTD		3469	-1418
NO LOG			

8-5/8" 255/210sx, 4 1/2" ³⁴⁶⁻ 2465/125sx
 NO DST'S
 MICT - CO, (REAG OH), SWB 3 1/2 BOPD,
 NO WTR, NAT, POP, P 20 BOPD, NO WTR

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS