

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22099-00-06<sup>01</sup>  
Spot: SESWNE Sec/Twnshp/Rge: 6-23S-4E  
2967 feet from S Section Line, 1742 feet from E Section Line  
Lease Name: STELLA LIGGETT Well #: 3  
County: BUTLER Total Vertical Depth: 2486 feet

Operator License No.: 32444  
Op Name: HIZEY SERVICE & SUPPLY, INC.  
Address: BOX 296  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2485		
SURF	8.625	200		
T1	2.375	2471		

80.80

Well Type: EOR UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2007 8:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 11/16/2007 4:00 PM

Witness Type: PARTIAL  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

11-13-2007, LAYED DOWN TBG & PACKER. 11-14-2007, SANDED BACK @ 2400'. 11-15-2007, SET CIBP @ 2395', DUMP BAILED 2 SXS CEMENT ON TOP. PARTED CASING @ 1830', LAYED DOWN 44 JTS 4-1/2" CASING (1830'). 11-16-2007, DUMP BAILED FLUID IN WELL @ 250', LAFORGE REDI-MIX, DUMPED 4.5 YARDS SLURRY MIX TO SURFACE. LAFARGE CEMENT TICKET #C04587112. P.A. COMPLETE 1600 PM 11-16-2007.

Perfs:

Top	Bot	Thru	Comments
2453	2457		


RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 29 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: E-22,487 -097.02950,38,08011, PERFS 2452'-2457'

Plugged through:

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

PKT