

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20179-00-00
Spot: CNWNESW Sec/Twnshp/Rge: 30-9S-21W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: CW SMITH Well Number: 2-D
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 6622
Op Name: JASON OIL COMPANY
Address: PO BOX 701 363 W 12TH ST
RUSSELL, KS 67665

Conductor Pipe: Size _____ feet: 8/30.33
Surface Casing: Size 8.625 feet: 247 ^{KCC} 165 SX CMT
Production: Size 5.5 feet: 4010 ³⁹⁶⁰ 150 SX CMT
Liner: Size _____ feet:

Well Type: SWD UIC Docket No: D21065.0 Date/Time to Plug: 02/07/2002 9:00 AM
Plug Co. License No.: 6622 Plug Co. Name: JASON OIL COMPANY
Proposal Rcvd. from: BILL LEIKAM Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
D.V. at 1150' set with 175 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/07/2002 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 5 1/2" and pumped 300 sxs cement with 600# hulls.
Max. P.S.I. 400#.

RECEIVED
FEB 11 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 12, 02

INV. NO. 2002061368

FEB 07 2002

11303505

CLINTON OIL COMPANY #2-D SMITH 30-9-21W
 WICHITA, KS. NW NE SW
 Contr. RAINS & WILLIAMSON OIL Cty. GRAHAM
 Geol. Pool UNNAMED POOL CONE
 E. 2346 KB Cm. 11/13/68 Cp. 1/30/69 IP SWDW/ARB 3960-61

API 15-065-20,179

LOG Tops	Depth	Datum
*ANH	1839	+ 507
HEEB	3516	-1170
TOR	3541	-1195
LKC	3558	-1212
BKC	3722	-1376
ARB	3895	-1549
LTD	3899	-1553
RTD	3961	-1615
*SMB TOP		

Csg. 8" 247/165 sx; 5 1/2" 3960/150sx
 DST 3553-69/90", 480' GIP, 240' MO, BHP
 1022-944#/30", FP 31-58#, FFP 72--93#
 DST 3582/3610/90", 240' GIP, 420' OIL SP SW,
 BHP 819-788#/30", FFP 135-228#
 DST 3608-28/1', 15'M, BHP 31-31#, FP 31-31#
 DST 3636-51/90", 70' MW W/SC O, BHP 1037--
 985#/30", FP 20-37#, FFP 41-52#
 DST 3686-3725/90", 40' OCM, BHP 227-122#/30"
 FP 27-42#, FP 52-59#
 DST 3874-98/30", 10'M, FBHP 41# FP 37-41#
 DST 3895-3901, PKR FAILED, 380'M, NO PRESS
 DST 3873-3902/60", 30'M, BHP 62-62#, FP 52-
 52#
 DST 3873-3910/90", 1540' SW, BHP 1140-1136#/
 30", FFP 572-991#
 CO TO 3960, PF 10/3559-62, A 5500

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS