

4-041618

9-26

E-13,518

KCCap

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-01623-00-01

SW NW NE /4 SEC. 11, 09 S, 19 W  
4290 feet from S section line  
2310 feet from E section line

Operator license# 5229

Lease Barry LKC Unit well #6W03

Operator: Phillips Petroleum Company

County Rooks

Address: 510 NW 3rd Street  
Plainville, Kansas 67663

Well total depth 3441 feet <sup>111.83</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 212 feet  
w/250 sxs.

Aband. oil well     , Gas well     , Input well X, SWD     , D & A     

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 26 Month: September Year: 94

Plugging proposal received from: Dave Stahl

Company: Phillips Petroleum Company Phone:                     

Were: 6" casing set @ 3431' w/300 sxs. cmt. Perf. @ 3187' - 3384'.  
Perf. @ 1200' and squeeze with 100 sxs. Holes in casing at 1416' - 1448'.  
Casing leaks at 1946' - 2607' squeeze with 400 sxs. 4-88: T.O.C. 2480'.  
(C.B.L. 05-06-88)  
Ordered 350 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 12:30P.M., Day: 26, Month: September, Year: 94

Actual plugging report: R.I.H. with tubing to 3380'. Pumped 100 sxs.  
cement with 250# hulls. Pulled to 2500' - Pumped 100 sxs. cement with  
100# hulls. Pulled to 1500' - Pumped 100 sxs. cement with 200# hulls.  
Circulated cement - pulled tubing - cement circulated and filled to  
surface. 10 3/4" S.P. Squeezed 40 sxs. cement plus 50# hulls.  
Max. P.S.I. 300#.

Remarks: C.I.B.P. at 3410' with 2 sxs. cement on top.  
Condition of casing(in hole): GOOD      BAD X Anhy.plug: YES X NO       
Bottom plug(in place): YES X, CALC.     , NO      Dakota plug: YES X, NO       
Plugged through TUBING X, CASING     . Elevation:      GL     

I did [X] / did not [    ] observe the plugging.

                    

**INVOICED**  
DATE 10-10-94  
INV. NO. 41377

                     (agent)  
Form CP-2/3