

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,325 ~~00-00~~ *KCC*
SW NE SW, Sec. 22, T 10 S, R 20 W/E *ag*

1650 feet from N/S section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9449 Lease Name Palmburg Well # 1

Operator: Great Eastern Energy and Development Corporation
Name & Address: 620 City Center Tower, 1801 California St., Denver, Colorado
County Rooks
Well Total Depth 3710 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman & Iannitti License Number 5122 Tag # 25

Address 1022 Union Center, Wichita, Ks. 67202

Company to plug at: Hour: 2:15 PM Day: 12th Month: April Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Vernon Dunlap

(company name) Woodman & Iannitti (phone) (316) 265-7650

were: 8 5/8" 267' SP CUC w/160 sks 60/40 pozmix 2% gel 3% cal. cl. (by Allied Cmt.)

Ordered 220 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk cello-flake and 8 5/8" plug, spot with drill stem, turn hole over, heavy mud between all plugs, no circulation problems, Elev. 2120 Anhy 1472 Arbuckle 3670'

Signed *Mason Schmidt*
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2:15 PM Day: 12 Month: April Year: 1984

ACTUAL PLUGGING REPORT Ordered 220 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk cello-flake and 8 5/8" plug spotted with drill stem, turned hole over, heavy mud between all plugs

1st plug @ 3630' w/25 sks cmt
2nd plug @ 1480' w/25 sks cmt
3rd plug @ 840' w/100 sks cmt. w/1 sk cello-flake
4th plug @ 270' w/50 sks cmt
5th plug solid bridge hulls plug @ 40' to 0 w/10 sks cmt.
Remarks: 10 sks in Rat Hole (Circulate)

Cemented by Allied Cmt. Co.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed *Mason Schmidt*
DOIC (TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 4-23-84

INV. NO. 1225

4-12 APR 26 1984