

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21108-00-00
Spqt: SWMENE Sec/Twnshp/Rge: 4-9S-28W
4270 feet from S Section Line, 1020 feet from E Section Line
Lease/Unit Name: CALDWELL Well Number: 2
County: SHERIDAN Total Vertical Depth: 4030 feet

Operator License No.: 30076

Conductor Pipe: Size feet: 130.98

Op Name: ANDERSON, ANDY DBA A & A PRODUC

Surface Casing: Size 8.625 feet: 221

Address: PO BOX 100
HILL CITY, KS 67642

Production: Size 4.5 feet: 4021

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/12/2002 8:00 AM

Plug Co. License No.: 30076

Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION

Proposal Rcvd. from: ANDY ANDERSON

Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-6266

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel.
Spot 60 sxs - bottom - 50 sxs at 250' - 15 sxs at surface.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/12/2002 10:30 AM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" casing set at 221' w/150 sxs cement. 4 1/2" set at 4021' w/150 sxs cement.
PBSD 4000'.
Stage collar at 2316' - not cemented.
Well tested - results non-commercial.
4 1/2" production casing cut and free at 1115' - spotted 60 sxs cement on bottom.
Pulled pipe to 250' - circulated with 50 sxs cement.
Pulled 4 1/2" pipe to surface - cemented with 15 sxs to top of pipe.
Plug completed at 10:30 A.M.
1115' of 4 1/2" casing recovered.
09-13-2002 - Follow-up inspection - cement drop of 100' from surface.

RECEIVED

SEP 20 2002
09-20-2002
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE

9-24-02

NO. INV.

2003060550

Form CP-2/3

SEP 13 2002

A & A PRODUCTION
HILL CITY KS 67642

4-09S-28W
4270' FSL & 1020' FEL, SEC

#2 CALDWELL

site 3-1/4 S OF HOXIE KS city: SHERIDAN API 15-179-21108
contr: A & A PRODUCTION #1 field: FREDA
gsd: JERRY GREEN
fr spd drtg card last
date 01/23/2002 date 01/28/2002 comp 02/07/2002 issued 06/17/2002 revised 06/17/2002

| | | | | |
|--|--|--|--|--|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

ELV: 2658 GL LOG
tops.....depth/datum
ANH.....2286 +372
HOW.....3450 -792
TOP.....3536 -878
HEEB.....3748 -1090
TOR.....3772 -1114
LANS.....3784 -1126
BKC.....4014 -1356
LTD.....4028 -1370
RTD.....4030 -1372

IP status:
OIL, LKC 3787-3828 OA, 04/15/2002
CSG: 8-5/8" 221 / 150 SX (ALT 2), 4-1/2" 4021 / 150 SX, MULTI
STAGE COLLAR AT 2316
COMMENT: MI & RURT 1/25/2002; DELAYED SPD TILL
1/28/2002
NO CORES
DSTS TAKEN; DETAILS NA
TRGT ZN: KC (OIL), PTD 4000 (KC), MICT - CO, PF (KC)
1/3817, 1/3828, AC 4000 GAL (15% NE), SWB LD, SO, PF
(LKC) 1/3787, 1/3817, 1/3828, 1/3854 & (TOR) 1/3776, AC 1500
GAL (15% MCA), SWB LD, SO, POP, OIL WELL (POTENTIAL
NOT RPTD), 4/15/2002 (PROD FROM LKC ONLY) - NO
OTHER INFO AVAILABLE - TEMP COMP 6/17/2002