

4-25

243

R

6 020527

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,958-00-00
SE NE NE, SEC. 9, T 9 S, R 28 W/E

4290 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30342
Operator: Sheets OOI Co.
Name & Address: 1333 W 120th Ave Suite 310
Westminster, Co. 80234
303-426-9722

Lease Name Billinger Well # 1-9
County Sheridan 136.50
Well Total Depth 4200 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 288 feet 8 5/8

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418
Address Box 1389, 1105 Walnut - Great Bend Kansas - 67530

Company to plug at: Hour: _____ Day: 25 Month: April Year: 19 90

Plugging proposal received from Craig Christopher

(company name) _____ (phone) 316-793-5681

were: Order 190 sks 60/40 poz 6% gel 3% cal cl lsk f.c. and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gilbert Balthazar (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:45AM Day: 25 Month: April Year: 19 90

ACTUAL PLUGGING REPORT
1st plug at 2410' w/25 sks
2nd plug at 1500' w/100 sks
3rd plug at 300' w/40 sks
4th plug at 40' w/10 sks wiper plug
15 sks in rathole

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90
VOL. NO. 28087

MAY 10 3 11 PM '90
05-03-1990

Signed Gilbert Balthazar (TECHNICIAN)

Gilbert Balthazar