

4 060101

7-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,965-00-00
SW NE, SEC. 20, T 9 S, R 30 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market Suite 1000
Wichita, KS 67202

Lease Name Baalman Well # 1
County Sheridan 137.80
Well Total Depth 4240 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, KS

Company to plug at: Hour: 1:00PM Day: 5 Month: July Year: 19 90

Plugging proposal received from Steve Carlton

(company name) Murfin Drilling Co. (phone) _____

were: Order 190 sxs. 60/40 pos 6% gel w/ floccul per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXXXXXX

Operations Completed: Hour: 1:00PM Day: 5 Month: July Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2510' with 25 sxs. Anhydrite 2493-2523'
2nd plug at 1640' with 100 sxs. Dakota 1338-1638'
3rd plug at 310' with 40 sxs. Surface pipe to 258'
4th plug at 40' with 10 sxs.
rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1990
07-11-1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-17-90

INV. NO. 28614

File S.

Signed Herb Deines
(TECHNICIAN)
Herb Deines