

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21110-00-00
Spot: NENWSE Sec/Twnshp/Rge: 20-9S-30W
2510 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BAALMAN Well Number: 1
County: SHERIDAN Total Vertical Depth: 4270 feet

Operator License No.: 5616

Surface Casing Size: 8.625 feet: 263 w/150 sxs cmt

Op Name: NOAH, CALVIN

Address: 329 N. BIRCH
VALLEY CENTER, KS 67147

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/17/2003 12:00 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ED MCKENNA

Company: MURFIN DRILLING CO., INC.

Phone: (308) 345-5010

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 08/17/2003 9:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 2550' w/25 sxs cement.
2nd. Plug at 1680' w/100 sxs cement.
3rd. Plug at 310' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.
15 sxs in rathole.
10 sxs in mousehole.
Total of 200 sxs 60/40 pozmix.

RECEIVED

08-26-2003
AUG 26 2003

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger Moses

(TECHNICIAN)

INVOICED

DATE 9-2-03

REF. NO. 2004060457

Form CP-2/3

AUG 22 2003