

6- 100462

10-19

138  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,047-00-00

NE NE NW /4 SEC. 28, 09 S, 30 W  
330 feet from S section line  
2310 feet from E section line

Operator license# 05184 Lease Moellering well # 1

Operator: Shields Oil Producers, Inc. County Sheridan

Address: Shield Building Well total depth 4075 feet <sup>132.44</sup>  
Russell, Kansas 67665 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 305 feet

Aband. oil well    , Gas well    , Input well    , SWD    , D & A X

Plugging contractor: Shields Drilling Co. License# 05184

Address: Russell, Kansas 67665

Company to plug at: Hour: ?? Day:     Month:     Year:    

Plugging proposal received from: Cliff Mayfield

Company: Shields Drilling Comp. phone:    

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

- 1st plug @ 2550 feet with 25 sacks Rat hole: 15 sacks
- 2nd plug @ 1690 feet " 100 " Mousehole: 10 sacks
- 3rd plug @ 350 feet " 40 "
- 4th plug @ 40 feet " Wiper plug & 10 sx.
- 5th plug @     feet "

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[     ], Part[     ], None[ X ]

Completed: Hour: 2:45 pm, Day: 19, Month: October, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2940 GL, Anhydrite depth: 2547 - 2580 feet  
Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: NO  
Plugged through drill pipe: YES  
Did NOT penetrate Arbuckle, cemented by Allied

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1992  
11-25-1992  
Wichita, Kansas

I did     did not X observe the plugging.

David K. Wann  
David K. Wann P.I.R.T. II  
(agent)

**INVOICED**

DATE 12-4-92  
INV. NO. 36972