

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-179-20,925-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Hinkle Oil Co. OPERATORS LICENSE NO. 5290

ADDRESS 1016 Union Center Wichita, KS 67202 PHONE # (316) 267-0231

LEASE (FARM) Pratt WELL NO. 1 WELL LOCATION 50' N E/2 W/2 SW/4 COUNTY Sheridan

SEC. 4 TWP. 9 RGE. 28= (~~E/2~~W) TOTAL DEPTH 4029' PLUG BACK TO _____

Check One: _____

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 292.90 CEMENTED WITH 180 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug @ 2300' w/25 sx. cement; 2nd plug @ 1325' w/100 sx cement, 15 sx. hulls; 3rd plug @ 350' w/40 sx. cement; 4th plug @ 40' w/wiper plug & 10 sx. cement. 15 sx. cement in rathole, All cement 60/40 posmix, 6% gel, 3% cc.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not, explain) To be sent by operator _____

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 2:00 a.m. 6-13-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Wilmer Dreiling PHONE # (913) 743-6308 JUN 21 1988

ADDRESS 408 Jefferson, Ellis, KS 67637 06-21-1988

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422
Wichita, Kansas

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 261-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: June 17, 1988