

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-21,046-00-00

LEASE NAME Popp

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2,970 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 14 TWP. 9 RGE. 27 (X) or (W)

COUNTY Sheridan

LEASE OPERATOR Staab Energy & Leasing

ADDRESS 2514 Haney Drive, Hays, KS. 67601

PHONE# (913) 628-1326 OPERATORS LICENSE NO. 03655

Date Well Completed 10-11-92

Character of Well D & A

Plugging Commenced 10-11-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-11-92

The plugging proposal was approved on 10-11-92 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,120'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	264'	Cmtd. w/190 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,340' thru drill pipe. Push bridge plug to 1,486', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 300', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Energy & Leasing

STATE OF KANSAS COUNTY OF RUSSELL

Jack P. Beeman

(Employee of Operator or Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of division facts statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 19 92

Ruth Phillips  
Notary Public

My Commission Expires:






Shields 15-179-21046-00-00 Russell, Kansas

WELL LOG

Operator: Staab Energy & Leasing  
Well: Popp #1  
Commenced: October 3, 1992  
Completed: October 11, 1992  
Contractor: Shields Drilling Co.

Well Description: SW SE NW  
Sec. 14-9S-27W  
Sheridan Co., KS.



Elevation: 2,736' KB  
Treatment:  
Production: D & A  
Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	264'	Cmtd. w/190 sax

..... Figures Indicate Bottom of Formations .....

Sand	267'
Shale & sand	2,332'
Anhydrite	2,364'
Shale	2,651'
Shale & lime	3,882'
Lime	4,120' RTD

Notes

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 28 1992  
CONSERVATION DIVISION  
Wichita, Kansas

10-28-1992