


15-179-20168-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Sheridan County. Sec. 13 Twp. 9 Rge. 28 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines SE SW SW  
Lease Owner Dreiling Oil, Inc.  
Lease Name Ochs Well No. 1  
Office Address Rt. #2, Victoria, Kansas 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed 1-19 19 69  
Application for plugging filed 2-2 19 73  
Application for plugging approved 2-6 19 73  
Plugging commenced 2-28 19 73  
Plugging completed 2-28 19 73  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 10-25 1973  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4185 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Casing			4 1/2"		4185'	1554'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 5 sacks Hulls, 9 Gel, 110 cu. ft. cement, 21 Gel, plug 30 cu. ft. cement, 5 Gel, 10 cu ft. cement, Input 400#, Shut In 200#.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 9 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
03-09-1973

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Russ Casing Pulling, Inc.  
Address P. O. Box 1082, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Joe Hess, Sec. Treas. of Drlg. Contrc. (employer of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess  
JOE HESS, Rt. #2, Victoria, Kansas 67671  
(Address)

Subscribed and sworn to before me this 7th day of March, 19 73

Cecilia Basgall  
CECILIA BASGALL Notary Public.



My commission expires September 13, 1976

# L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG 15-179-20168-00-00

Company **Dreiling & Hiko Bell Mining & Oil Company**  
Route 2  
Victoria, Kansas 67671  
Sec. 13 Twp. 9 Rng. 28

Farm **Ochs** No. 1  
Location **SE SW SW**

Total Depth **4185'**  
County **Sheridan**

Comm. **1-11-69** Comp. **1-19-69**  
Elevation: **2779'** K. B.  
**2776'** D. F.  
**2774'** G. R.

Contractor **L. J. Dreiling & Sons, Inc.**  
Victoria, Kansas 67671

Casing Record

280' - 8 5/8"  
4106' - 4 1/2"

Cement Record

150 sacks cement  
150 sacks 50/50 pozmix, 2% gel,  
10% salt, 1% CC, 6# Friction Reducer  
10 bbls. chemical flush ahead of  
cement

Production:


Figures Indicate Bottom of Formations

0'	50' Surface Clay	
50'	197'	Sand
197'	230'	Yellow Clay
230'	280'	Blue Shale
280'	1275'	Shale
1275'	1883'	Shale
1883'	2240'	Shale & Sand
2240'	2325'	Shale
2374'	2421'	Anhy.
2421'	2544'	Shale
2544'	2650'	Shale & Shells
2650'	2940'	Shale & Shells
2940'	3020'	Shale
3020'	3225'	Shale & Lime
3225'	3345'	Shale & Chalk
3345'	3685'	Shale & Lime
3685'	4185'	Lime
4185'	T.D.	

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 6 1973  
02-06-1973  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS)  
                          )ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Ochs #1.

  
LEO F. DREILING

Subscribed and sworn to before me this 21st. day of January 1969.

  
JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970

