

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-179-20674-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Sheridan SEC. 13 TWP. 9 RGE. 28 E/W
 Location as in quarters or footage from lines:
 SE NW NW

Lease Owner Energy Three Inc.
 Lease Name OCHS Well No. 1
 Office Address Box 1505, Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): dry
 Date Well Completed 2-14-83
 Application for plugging filed 2-14-83
 Plugging commenced 2-14-83
 Plugging completed 2-14-83
 Reason for abandonment of well or producing formation dry

Locate Well
 correctly on above
 Section Plat.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4152'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

- 6% gel 3% cc
- 190 sx 50/50 pos mix
- 20 sxs @ 2380
- 100 sxs @ 1500
- 40 sxs @ 350
- 40 sxs @ 40' 1/2 sx hulls
- 10 sxs rathoade 10 sxs mousehole

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Allied Cementing

STATE OF Kansas COUNTY OF Russell, ss.
Tim Scheck (employee of owner) or (owner or operator) of the
 above-described well, being **RECEIVED** sworn on oath, says: That I have knowledge of the
 facts, statements, and **STATE CORPORATION COMMISSION** and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

FEB 22 1983
02-22-1983
 CONSERVATION DIVISION
 Wichita, Kansas

(Signature) Timothy T. Scheck
Box 52, Gosham, Kansas 67640
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 19 83



Joan Weigel
 Notary Public.

My Commission expires: January 19, 1985

15-179-20674-00-00

BIG THREE Drilling, Inc.

Tim Scheck, President
Larry Langhofer, Tool Pusher

DRILLING SERVICES TO 5,000 FEET IN KANSAS AREA

South Clifford, Box 52
Gorham, Kansas 67640


Company	Energy Three Inc.
Farm	OCHS #1
Location	SE NW NW 13-9-28W
County	Sheridan
Contractor	Big Three Drilling Inc.
Comm	2-7-83
Compl	2-14-83
Total Depth	4152 R.T.D.
Casing	Dry
Production	Dry

Figures Indicate Bottom of Formation

Sand & Clay	295'
Sand & Shale	1570'
Lime & Shale	2311'
Anhydrite	2380' to 2418'
Shale & Lime	4077'
Lime	4100'
Shale & Lime	4152'

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Big Three Drilling Inc.



Timothy F. Scheck

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1983

CONSERVATION DIVISION
Wichita, Kansas