

15-179-20452-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sheridan County. Sec. 15 Twp. 9 Rge. 28 EXW  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW/SE/NW

Lease Owner John O. Farmer, Inc.  
Lease Name Kennedy Well No. 2  
Office Address Box 352, Russell, KS 67665  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Oil  
Date Well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 10 19 78  
Plugging completed November 27 19 78  
Reason for abandonment of well or producing formation

Depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4190'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	272'	NONE
				4 1/2"	4077'	1463.22'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped sand to 3900' with four (4) sacks cement.  
Shot casing at 3300'; spotted 90 bbls oil behind casing.  
Shot casing at 2500', 2000', 1800', 1600', and 1500'.  
Pulled 36 joints of 4 1/2" casing.  
Squeezed well with three (3) sacks hulls, 70 sacks 50/50 pozmix cement with 6% added gel, 14 sacks gel, and 60 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
James W. Rockhold Bx 698, Gt. Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 28<sup>th</sup> day of November, 1978

STATE NOTARY PUBLIC  
CATHY L. COLE  
Barton County, Kansas  
My Appt. Exp. June 14, 1982

Cathy L. Cole  
Notary Public.

My commission expires

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1978  
11-30-1978  
CONSERVATION DIVISION  
Wichita, Kansas