

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER. 15-179-20,902 ~~00-00~~

LEASE NAME Kennedy

WELL NUMBER 1-15

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 15 TWP. 9S RGE. 28 ~~XXXXXX(W)~~

COUNTY Sheridan

Date Well Completed 8-11-87

Plugging Commenced 8-11-87

Plugging Completed 8-11-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Walter A. Ohmart, Jr.

ADDRESS 1580 Lincoln St, Suite 1180, Denver, CO 80203

PHONE#(303) 830-0197 OPERATORS LICENSE NO. 03448

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District 6 Carl Goodrow

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	276	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump mud to 2450' set 1st plug from 2450' to 2350' w/25 sx; pump mud to 1500' set 2nd plug from 1500' to 1100' w/100 sx; pump mud to 325' set 3rd plug from 325' to 165' w/40 sx; pump mud to 40' set wiper plug and cement to surface w/10 sx. Pump 15 sx in rathole and pump 10 sx in mousehole. All cement 60/40 posmix, 6% gel, 3% cc

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of August, 19 87

RECEIVED

STATE CORPORATION COMMISSION

Notary Public

Commission Expires: Dec. 29, 1990

AUG 17 1987
08-17-1987

CONSERVATION DIVISION
Wichita, Kansas

