

15-179-20363-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 26 Twp. 9 Rge. 28W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE NW SW

Lease Owner Rupe Oil Company
Lease Name Miller Well No. 1
Office Address 925 Olive Garvey Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9/11/73 19
Application for plugging filed 9/11/73 19
Application for plugging approved 9/11/73 19
Plugging commenced 9/14/73 19
Plugging completed 9/14/73 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4146 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	218'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe at 1200' w/70 sacks cement.
Plugged through drill pipe at 210' w/30 sacks cement.
Bridge plug at 40' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1973
09-18-1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 17th day of September, 1973
Virginia S. Fabian
Notary Public.

15-179-20363-00-00

WELL LOG

RUPE OIL COMPANY
925 Olive Garvey Building
Wichita, Kansas 67202

#1 MILLER
NE NW SW Sec. 26-9-28W
Sheridan County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Set 212' of 8 5/8" w/160
sacks common quick set cement.

COMMENCED: 9/1/73
COMPLETED: 9/11/73

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Gravel	0	249	2765 Gr.
Blue Shale	249	285	2767 D.F.
Shale & Shale	285	1445	2770 K.B.
Sand & Shale	1445	2370	
Anhydrite	2370	2404	
Shale & Shells	2404	2780	
Shale & Shale	2780	2985	
Shale & Shells	2985	3114	
Shale & Lime	3114	3220	
Sime & Shale	3220	3960	
Lime	3960	3984	
Lime & Shale	3984	4142	
Lime	4142	4146	
Total Depth	4146		

FORMATION TOPS

Anhydrite	2370 +	400
Base Anhy.	2402 +	368
Topeka	3658 -	888
Heebner	3875 -	1105
Toronto	3897 -	1127
Lansing	3912 -	1142
R.T.D.	4146 -	1376

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NW SW of Section 26-9-28W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF-DRILLING-CO., INC.

Jim Robinson
Jim Robinson, Office Manager

Subscribed and sworn to before me this 13th day of September, 1973.

Virginia S. Fabian
Virginia S. Fabian, Notary Public

MY COMMISSION EXPIRES:
August 5, 1973

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1973
09-18-1973
CONSERVATION DIVISION
Wichita, Kansas

