

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20,793-00-00

LEASE NAME Adams #1

WELL NUMBER _____

SPOT LOCATION NW NW NE

SEC. 30 TWP. 9s RGE. 28w(E) of (N)

COUNTY Sheridan

Date Well Completed 3-8-85

Plugging Commenced 10/10/85

Plugging Completed 10/29/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Frontier Oil Co.

ADDRESS 1720 KSB Bldg. Wichita, Ks. 67202

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140

Character of Well Oil.
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing-KC Depth to top 3983' bottom T.D. 4250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Clay, shale	170sx, 60-40 Poz, 2% gel, 3% cc.	-0-	260'	8 5/8"	260'	none
Lime, shale.	190 sx Common, 10% salt	-0-	4242'	4 1/2"	4242'	1647'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4098' & 4 sacks cement. Shot pipe at 3211', 2908', 2717', 2630', 2535', 2327', 2116', 1841', & 1647'. Pulled 39 joints of pipe.

Plugged well with 2 hulls, 50 cement with 1 hull, 12 gel with 1 hull, 100 cement with 2 hulls, 28 gel with 2 hulls, released plug, & 50 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 85

RECEIVED
STATE CORPORATION COMMISSION
Notary Public

My Commission expires:



NOV 27 1985
11-27-1985

CONSERVATION DIVISION

Form CP-4
Revised 01-84