

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-20,827  
LEASE NAME Adams  
WELL NUMBER #2  
SPOT LOCATION C-S/2 S/2 NE/  
SEC. 30 TWP. 9S RGE. 28W (E) or (W)  
COUNTY Sheridan  
Date Well Completed 6-19-85  
Plugging Commenced 6-19-85  
Plugging Completed 6-19-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Frontier Oil Company  
ADDRESS 125 N. Market, Ste 1720, Wichita, Ks. 67202  
PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140.

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dale Balthazor.

Is ACO-1 filed? Yes If not, is well log attached? (Not logged).

Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 4210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale & Sand.	170sx 60-40 Poz, 2% gel 3% cc.	-0-	259'	8-5/8"	252.88'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged @ 2450' / 25 sx, 1220' / 100sx, 280' / 40sx, solid bridge plug @ 40' / 10sx, 10sx in rat hole.  
Plugged with 185 sx 50-50 Poz, 2% gel 3% cc.  
(Plugs calculated by displacement).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. N/A  
Address P O Box 31, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jean Angle (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Jean Angle

(Address) 125 N. Market, Ste 1720, Wichita, Ks.

RECEIVED  
JUN 16 1985  
07-16-1985  
CONSERVATION DIVISION  
SUBSCRIBED AND SWORN TO before me this 15th day of July, 1985

Stella Sewell  
Notary Public



Witness: June 24, 1988