

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20217-00-00

LEASE NAME Pratt Estate #1

WELL NUMBER _____

SPOT LOCATION E/2 SE SE

SEC. 1 TWP. 9s RGE. 29w(E) or (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 2/7/86

Plugging Completed 2/13/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chief Drilling Co. Inc.

ADDRESS 151 N Main Suite 700, Wichita, Ks. 67202

PHONE # (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4085'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	229'	none
				5 1/2"	4083'	1409'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3774', & 5 sacks cement. Shot pipe at 2811', 2517', 2227', 2039', 1812', 1621', & 1409'. Pulled 43 joints of pipe. Pumped well with 3 hulls, 22 gel, 100 cement, 18 gel, released plug, & pumped 80 sacks 60/40 poz 6% gel 3% c.c. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 21st day of February, 19 86

My Commission expires:



STATE CORPORATION COMMISSION Notary Public

FEB 24 1986
02-24-1986
CONSERVATION DIVISION

Form CP-4
Revised 01-84

GREAT GUNS

R/A Log

FRING NO.	15-179-20217-00-00	
	COMPANY CHIEF DRILLING COMPANY	
	WELL PRATT ESTATE NO. 1	
	FIBD WILDCAT	
COUNTY SHERIDAN		STATE KANSAS
LOCATION: E/2 SE SE		OTHER SERVICES:
SEC	1 TWP	9S RGE 29W

PERMANENT DATUM: GROUND LEVEL	ELEV. 2722'	ELEV. K.O. 2777'
LOG MEASURED FROM KELLY BUSHING	5 FT. ABOVE PERM. DATUM	D.F. 2725'
DRILLING MEASURED FROM KELLY BUSHING		G.I. 2722'

DATE	7.8.69		
RUN NO.	ONE		
TYPE LOG	ACID SURVEY		
DEPTH - DRILL	3980'		
DEPTH - LOGGED	3980'		
BOTTOM LOGGED INTERVAL	3980'		
TOP LOGGED INTERVAL	3750'		
TYPE FLUID IN HOLE	WATER		
SALINITY, PPM CL			
DENSITY			
LEVEL			
MAX. REC. TEMP., DEG F.			
OPERATING RIG TIME	ONE HOUR		
RECORDED BY	AL MUNDAY		
WITNESSED BY	L. LINDEMUTH		

BORE-HOLE RECORD				CASING RECORD			
RUN NO.	DIT	FROM	TO	SIZE	WGT.	FROM	TO

RECORDED
STATE CORPORATION COMMISSION
JAN 21 1986
01-21-1986
CONSERVATION DIVISION