

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20229-00-00

LEASE NAME Pratt Estate #2

WELL NUMBER _____

SPOT LOCATION SE NE SE

SEC. 1 TWP. 9 RGE. 29W (E) or (W) (W)

COUNTY Sheridan

Date Well Completed _____

Plugging Commenced 2/4/86

Plugging Completed 2/13/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 151 N. Main, Suite 700, Wichita, Ks. 67202

PHONE # (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4044'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	214'	none
				5 1/2"	4042'	499'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3790' & 5 sacks cement. Shot pipe at 2630', & 2035'.
Pipe parted. Pulled 499' of pipe. Plugged well with 3 hulls, 22 gel, 100
cement, 18 gel, plug, & 80 sacks 60/40 poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 20th day of February, 19 86

My Commission expires:



RECEIVED
FEB 24 1986
02-24-1986
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84

15-179-20229-00-00

WELL LOG

Chief Drilling Co., Inc.
905 Century Plaza
Wichita, Kansas 67202

#2 PRATT ESTATE
SE NE SE Sec. 1-9-29W
Sheridan County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-1-69
Completed: 9-9-69

Casing Record: 8 5/8" set @ 214' w/165 sacks cement.
5 1/2" set @ 4042' w/200 sacks 60/40 Pozmix

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay	0	30	2722 Gr.
Surface clay & sand	30	80	2724 D.F.
Shale & sand streaks	80	1734	2727 K.B.
Shale, shells & red bed	1734	2006	
Sand	2006	2129	
Red bed, shale & sand	2129	2341	
Anhydrite	2341	2374	
Shale & shells	2374	2545	
Shale & lime	2545	2965	
Shale, shells, & lime	2965	2995	
Shale & lime	2995	3630	
Lime	3630	3838	
Lime & shale	3838	3868	
Lime	3868	4044	
Total depth	4044		

<u>FORMATION TOPS</u>	
Anhydrite	2333 + 394
Howard	3445 - 718
Heebner	3789 - 1062
Toronto	3807 - 1080
Lansing	3824 - 1097
B-KC est.	4069 - 1342
T.D.	4044 - 1317

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE NE SE of Section 1-9-29W, Sheridan County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 15th day of September, 1969.

Betty Brandt
Betty Brandt, Notary Public

My Commission Expires:
May 9, 1971

RECEIVED
STATE CORPORATION COMMISSION

JAN 21 1986
01-21-1986
CONSERVATION DIVISION