

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-21,016-00-00

LEASE NAME Deward Reitcheck

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 3 TWP. 9S RGE. 29 (E) (W)

COUNTY Sheridan

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P. O. Box 352, Russell, KS 67665

PHONE# (913) -483-3144 OPERATORS LICENSE NO. 5135

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7/18/91

Plugging Commenced 7/18/91

Plugging Completed 7/18/91

The plugging proposal was approved on 7-18-91 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4197'

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	302'	-0-

JUL 23 1991  
07-23-1991  
CORPORATION DIVISION  
WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4197'-2450' 10 sks cement @ 40'  
25 sks cement @ 2450' 15 sks in rathole  
100 sks cement @ 1520'  
40 sks cement @ 350'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 19 91

GLEND A. R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

Glenda R. Tiffin  
Glenda R. Tiffin, Notary Public

Commission Expires: February 6, 1992

15-179-21016-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1991  
07-23-1991  
CONSERVATION DIVISION  
Wichita, Kansas

EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: John O. Farmer, Inc.  
P. O. Box 352  
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Reitcheck WELL #1

LOCATION: SE SE SE  
Section 3-9S-29W  
Sheridan County, Kansas

ROTARY TOTAL DEPTH: 4197'

ELEVATION: 2814' K.B.

COMMENCED: 7/11/91

COMPLETED: 7/18/91

CASING: 8-5/8" @ 302' w/200 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Cedar Hills	125'	Toronto	3918'
Shale	225'	Lansing-Kansas City	3934'
Anhydrite	2440'	Base Kansas City	4181'
Shale	2476'	R.T.D.	4197'
Heebner	3895'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on July 22, 1991.

My commission expires: February 6, 1992.

  
GLEND A. R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-92

  
\_\_\_\_\_  
Glenda R. Tiffin, Notary Public