

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-179-00145-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sheridan County, Sec. 5 Twp. 9 Rge. 29 ~~(E)~~ (W) X

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines SE SE NE  
Lease Owner Empire Drilling Company  
Lease Name Patmon Well No. 1  
Office Address 650 Fourth National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 22, 1959 19  
Application for plugging filed July 22, 1959 19  
Application for plugging approved July 22, 1959 19  
Plugging commenced July 22, 1959 19  
Plugging completed July 22, 1959 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. H Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4525 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	253	8 5/8"	244'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug set @ 550' w/ 20 sx cement  
Plug set @ 240' w/ 20 sx cement  
Plug set @ 40' w/ 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
07-31-1959  
JUL 31 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company  
Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Dan J. Kornfeld

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
650 Fourth National Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of July, 19 59

My commission expires October 21, 1962

Lucille H. Harr  
Notary Public.

P 3  
FILE SEC 5 19 R 294  
BOOK PAGE 56 LINE 25

15-179-00145-00-00

LOG

ALL INFORMATION CONTAINED  
HEREIN IS UNCLASSIFIED  
DATE 07-31-1959 BY 10459  
DIVISION

COMPANY: Empire Drilling Company  
 CONTRACTOR: Empire Drilling Company  
 FARM: Patmon # 1  
 LOCATION: SE SE NE of Section 5-9S-29W, Sheridan County, Kansas  
 COMMENCED: July 13, 1959 ELEVATION: 2857 KB  
 COMPLETED: July 22, 1959 POTENTIAL: D & A

\*\*\*\*\*

0	to	253	Surface
253	to	2484	Shale-Shells
2484	to	2521	Anhydrite
2521	to	3055	Shale-Shells
3055	to	3450	Shale-Lime
3450	to	3515	Lime-Shale
3515	to	3695	Shale-Lime
3695	to	3820	Shale-Lime Streaks
3820	to	3930	Shale-Lime
3930	to	4197	Lime
4197	to	4265	Lime=Shale
4265	to	4360	Shale
4360	to	4410	Shale-Lime
4410	to	4465	Shale
4465	to	4515	Shale-Lime=Chert
4515	to	4525	Lime
4525			MTD

Set: 244 8 5/8" casing with 125 sacks cement


ELECTRIC LOG TOPS:

Anhydrite	2483	+ 374
Heebner	3929	-1072
Toronto	3952	-1095
Lansing	3970	-1113
Base Kansas City	4209	-1352
Cherokee Group	4365	-1508
Basal Pennsylvanian Conglomerate	4502	-1645
Mississippian	4507	-1650
Schlumberger Total Depth	4524	

\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Patmon # 1, SE SE NE of Section 5-9S-29W, Sheridan County, Kansas, as reflected by the files of Empire Drilling Company.



*Dan J. Kornfeld*  
Dan J. Kornfeld

Subscribed and sworn to before me, a notary public within and for Sedgwick County, Kansas, this 30th day of July, 1959.

PLUGGING  
 FILE SEC. 5 T. 9 R. 29W  
 BOOK PAGE 56 LINE 25

*Lucille H. Harr*  
Lucille H. Harr