


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 5 Twp. 9S Rge. (E) 29 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW

Lease Owner Koch Exploration Co.

Lease Name Patmon Well No. 1

Office Address P. O. Box 2256, Wichita, Kansas 67201

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Sept. 16, 1968

Application for plugging filed (letter 9/18/68) Sept. 16, 1968

Application for plugging approved Sept. 16, 1968

Plugging commenced Sept. 16, 1968

Plugging completed Sept. 16, 1968

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well 4230 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	RECEIVED STATE CORPORATION COMMISSION SEP 19 1968 CONSERVATION DIVISION Wichita, Kansas 09-19-1968	0	231	8-5/8"	231'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1150 feet. Set first plug @ 1150 feet with 100 sacks cement. Filled hole with heavy mud to 245 feet. Set second plug @ 245 feet with 1/2 sack hulls and 10 sacks cement. Filled hole with heavy mud to 40 feet. Set third plug @ 40 feet with 10 sacks cement. Job complete @ 2:00 A.M., September 16, 1968. Used Halliburton pump truck. Spotted cement through drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of September, 1968

February 1, 1972

Barbara J. Layton
Barbara J. Layton Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

PATMON #1
 SE NE SW Section 5-9S-29W
 Sheridan County, Kansas

15-179-20133-00-00

Commenced: September 6, 1968
 Completed: September 16, 1968

OPERATOR - Koch Exploration Co.

DEPTH		FORMATION	REMARKS
From	To		
0	35	Surface clay	
35	105	Sand	
105	128	Shale	
128	210	Shale and sand	
210	231	Shale	Ran 12 joints 8-5/8" casing, set @ 231' w/210 sacks cement.
231	800	Shale	
800	1000	Shale and shells	
1000	1225	Shale	
1225	1765	Shale and sand	
1765	2201	Shale	
2201	2295	Sand	
2295	2501	Shale and red bed	
2501	2537	Anhydrite	
2537	2865	Shale	
2865	3325	Lime and shale	
3325	3396	Lime and shale with chert	
3396	3485	Lime and shale	
3485	3580	Lime	
3580	3974	Lime and shale	
3974	4230	Lime	
4230	TD		Dry and abandoned.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 19 1968
 CONSERVATION DIVISION
 Wichita, Kansas

09-19-1968

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SE NE SW Section 5-9S-29W, Sheridan County, Kansas, to the best of my knowledge and belief.




 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18th day of September, 1968, personally appeared E. E. HALL to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972.



 Barbara J. Layton, Notary Public

