


15-193-20011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Thomas County, Sec. 16 Twp. 9S Rge. (E)32 (W)
Location as "NE/CNW%SW%" or footage from lines C SW SE
Lease Owner Trend Exploration Limited
Lease Name Page Well No. 1
Office Address 600 Capital Life Center, Denver, Colo. 80203
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 13, 1969
Application for plugging filed (letter 3/18/69) March 13, 1969
Application for plugging approved March 13, 1969
Plugging commenced March 13, 1969
Plugging completed March 13, 1969
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	278	8-5/8	278'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 1775 ft. Set first plug at 1775 ft. w/70 sacks cement.
Filled hole with heavy mud to 310 ft. Set second plug at 310 ft. w/20 sacks cement.
Filled hole with heavy mud to 40 ft. Set third plug at 40 ft. w/10 sacks cement.
Used pump truck to pump cement through drill pipe. Job complete at 9:30 A.M.,
March 13, 1969.

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1969
CONSERVATION DIVISION
Wichita, Kansas
03-19-1969


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830-Sutton-Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of March, 19 69



Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton Notary Public.

15-193-20011-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

PAGE #1
C SW SE Section 16-9S-32W
Thomas County, Kansas

Commenced: February 28, 1969
Completed: March 13, 1969

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1969
CONSERVATION DIVISION
Wichita, Kansas

03-19-1969

OPERATOR - Trend Exploration Limited

DEPTH		FORMATION	REMARKS
From	To		
0	45	Soil and clay	
45	95	Shale and sand	
95	278	Shale	Ran 14 joints 8-5/8" casing, set @ 278' w/200 sacks cement.
278	1300	Shale	
1300	1977	Shale and shells	
1977	2103	Shale and sand	
2103	2335	Shale and shells	
2335	2620	Shale and red bed	
2620	2666	Anhydrite	
2666	3665	Shale and lime	
3665	3765	Lime	
3765	4130	Lime and shale	
4130	4181	Lime	
4181	4385	Lime and shale	
4385	4453	Lime	
4453	4514	Lime and shale	
4514	4740	Lime	
4740	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW SE Section 16-9S-32W, Thomas County, Kansas to the best of my knowledge and belief.

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18 day of March, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972.

Barbara J. Layton, Notary Public

