


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Thomas County, Sec. 19 Twp. 9 Rge. (E) 32 (W)

Location as "NE/CNW/SW" or footage from lines NE-SW-SW
Lease Owner Quality Supply Co.
Lease Name D. Keller "A" Well No. 1
Office Address Yox Petroleum Bldg, Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-7 1961
Plugging completed 1-14 1961
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. FABRICUS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4675 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	480	NONE
				7"	4670	Y381

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Sanded hole to 4650- dumped 3 sks cement-
Hole would not load w/ water - set Plug @
3700'- dumped 3 sks cement - pulled casing -
Mudded hole to 470' - set 10' Rock Bridge -
dumped 75 sks cement - Mudded hole to
25' - set 5' Rock Bridge - dumped 10 sks
Cement to base of collar

STATE OF KANSAS
JAN 27 1961
CONSERVATION DIVISION
WICHITA, KANSAS
01-27-1961

Name of Plugging Contractor R + D Casing Pulling Co License # 736
Address Box 154, Ellinwood, Kans.

STATE OF Kansas COUNTY OF Sedgewick, ss.
Jack Shear (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Jack Shear
(Address) _____

Subscribed and sworn to before me this 26th day of January, 1961
My commission expires June 1, 1963
Lee Mankin Notary Public.



EXPLORATION RECORD

- 1 - Bvll. Prod.
- 1 - Division
- 1 - District
- 1 - Geological Dept. - Bvll.
- 1 - Geological Dept. - District

Quality Supply Co

15-193-00024-00-00

Lease Keller "A"

Well 1

Formation Name	Top	Base	Remarks
Sand	0	80	
Sand and shale	80	430	
Shale	430	1670	
Shale and shells	1670	2080	
Sand and shale	2080	2180	
Shale and shells	2180	2320	
Shale	2320	2372	
Hard chalk	2372	2378	
Redbed and shale	2378	2645	
Anhydrite	2645	2675	
Anhydrite, shale and lime	2675	2835	
Redbed, shale and lime streaks	2835	2975	
Shale and lime streaks	2975	3027	
Lime and shale	3027	3245	
Lime, shale, and pyrite	3245	3358	
Lime and shale	3358	3400	
Lime	3400	3435	
Lime and cherty shale	3435	3510	
Chert, granite, pyrite, and quartzite	3510	3530	
Lime, chert, and pyrite	3530	3567	
Lime and shale streaks	3567	3654	
Lime and shale	3654	3715	
Lime, shale, pyrite and chert	3715	3830	
Lime	3830	3950	
Lime and shale	3950	4045	
Shale, lime, pyrite and chert	4045	4135	
Lime	4135	4187	
Lime and shale	4187	4480	
Lime	4480	4501	*DST
Lime and shale	4501	4555	
Lime, shale, and chert	4555	4645	
Shale	4645	4648	
Lime, shale and chert	4648	4657	**Cored
Lime	4657	4717	*DST **Cored
Lime and shale	4717	4745	

FORMATION TOPS:

Howard	3837
Topeka	3866
Heebner	4042
Toronto	4063
Lansing-Kansas City	4081
Base Kansas City	4390
Marmaton	4411
Cherokee	4536
Mississippian	4680
Total Depth	4745

*See Daily Report Detailed.
 **See Daily Report Detailed.
 ***Not penetrated at 4745' TD.

REPT
 STATE COM
 DIVISION
 JAN 27 1961
 01-27-1961
 CONSERVATION DIVISION
 WICHITA, KANSAS