

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,602-00-00

LEASE NAME Renner

WELL NUMBER 2

3,630 Ft. from S Section Line

3,960 Ft. from E Section Line

SEC. 22 TWP. 9 RGE. 32 (X) or (W)

COUNTY Thomas

Date Well Completed 11-7-92

Plugging Commenced 11-7-92

Plugging Completed 11-7-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Kansas 67665

PHONE#(913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-7-92 (date)

by Bruce Basye (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,680'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	287'	Cmtd. w/195 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 25 sax cement @2,670' thru drill pipe. Spot 100 sax cement @1,830' thru drill pipe. Spot 40 sax cement @340' thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug torcellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Cement is 60-40 Pozmix w/6% jel and 2 sax flo-seal.

(If additional description is necessary, use BACK of this form.)

Plug down at 12:30 PM

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas (Employee of Operator) or Contractor of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS.

SUBSCRIBED AND SWORN TO before me this 18th day of November, 19 92

Jill A. Jones
Notary Public



Commission Expires: April 20, 1994




15-193-20602-00-00
Shields

Russell, Kansas

WELL LOG

Operator: John O. Farmer, Inc.
Well: Renner #2
Commenced: October 29, 1992
Completed: November 7, 1992
Contractor: Shields Drilling Co.

Well Description: N/2 S/2 NW
Sec. 22-9S-32W
Thomas County, KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	287'	Cmtd. w/195 sax

Elevation: 3,078' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand	290'
Shale	1,600'
Shale & sand streaks	2,127'
Shale	2,368'
Shale & Sand	2,657'
Anhydrite	2,687'
Shale	3,172'
Shale & lime	4,216'
Lime	4,680' RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 24 1992

Notes