

4-071088

2-23

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-22097-00-00

SE SE NE /4 SEC. 31, 10 S, 16 W
2970 feet from S section line
330 feet from E section line

Operator license# 7076 Lease George well # 4

Operator: Black Diamond Oil, Inc. County Rooks

Address: 3004 Broadway Aveune Well total depth 3550 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Ken Vehige Surface pipe 8 5/8 Inch @ 204 feet

115.37

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 23 Month: February Year: 94

Plugging proposal received from: Ken Vehige

Company: Black Diamond Oil Company Phone: 913-625-5891

Were: 8 5/8" - 204' cwc w/120 sxs. cement. 4 1/2" casing set @ 3550'
w/250 sxs. cement. PBDT @ 3481'. Perfs. 3092' - 3468'. Elv. 1953' -
Anhy. 1172'. Dakota 353' - 653'. Cedar Hills 685' - 875'. TD 915'.
Black Diamond tried to wash down well. Went out of hole at 640' drilled
to 915' - couldn't get any deeper. Don Butcher - KCC Supervisor, gave
permission to plug out well at that 915' depth. Proposal 200 sxs. Class
A common - 250 sxs. 65/35 pozmix - 6% gel. Spot all cement and circulate
through tubing. Load 4 1/2" x 8 5/8" annulus with cement.
Plugging Proposal Received by: Don Butcher - Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:45P.M., Day: 23, Month: February, Year: 94

Actual plugging report: Ordered 200 sxs. Class A common cement and 250
sxs. 65/35 pozmix - 6% gel. Pumped in with pump truck. Spotted and
displaced all cement through tubing. Don Butcher, KCC Supervisor,
gave permission to plug at 915'. 1) 2 3/8" tubing at 915' w/100 sxs.
Class A cement circulated out of 4 1/2" casing. 2) 2 3/8" tubing at 915'
shut in on top squeezed with 130 sxs. Class A common. 3) Squeezed 4 1/2"
x 8 5/8" annulus with 150 sxs. cement. Max. pressure 200# P.S.I. Shut in
100#. 4) Squeezed 4 1/2" casing w/25 sxs. cement. Max. pressure 400#
P.S.I. Shut in 400#. All but one joint of tubing lost in hole - 885'.

Remarks: Cemented by Allied Cement - Hays, Kansas
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1958 GL

I did did not observe the plugging.

Marion J. Schmidt
(agent)

RECEIVED
STATE CORPORATION COM
MAR 09 1994
03-09-1994
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 3-11-94

INV. NO. 40088
2-23