

4-1

4-041904

15-163-20006-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 3-10-1967

70
6-2-97 SW SW NW /4 SEC. 32 , 10 S, 16 W
2340 feet from N section line
320 feet from W section line

Operator license# 7076

Lease: George Well # 2

Operator: Black Diamond Oil, Inc.

County: Rooks 114,03

Address: Box 641
Hays, Kansas 67601

Well total depth 3570 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet
w/cwc.sx cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 1 Month: April Year 1997

Plugging proposal received from: Ken Vehige

Company: Black Diamond Oil, Inc. Phone: 913-625-5891

Were: 4 1/2" casing set at 3597' w/150 sxs cement. Perf at 3167' - 3570'.
Salt at 2000' - Anhy. At 1300' - Dakota at 700'.
Ordered 265 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:30 P.M., Day: 1, Month: April, Year: 1997

Actual plugging report: R.I.H. with tubing to 2000'. Spotted 80 sxs cement with 300# hulls.
Pulled to 1000'. Spotted 80 sxs cement with 200# hulls to circulate cement at surface.
Pulled tubing and squeezed casing with 55 sxs cement. Max. P.S.I. 700#. S.I.P. 300#.
Squeezed 8 5/8" S.P. with 50 sxs cement. Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
KANSAS CORPORATION COMMISSION

09-01-1997
JUL 01 1997

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING
Any plug: YES X NO
Dakota plug: YES NO
Elevation: G.L.

I did X / did not [] observe the plugging.

Dennis Hamel
(agent)

Form CP-2/3

INVOICED
DATE 7-1-97
INV. NO. 48436

100