

4-031776

10-13 35
15-065-01543-00-00 R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1955

NE SW NE /4 SEC. 32 , 09 S, 22 W
3630 feet from S section line
1650 feet from E section line

Operator license# 6273

Lease Sturgeon well # 2

Operator: Robert R. Price Oper., Inc.

County Graham

Address: Box 470442
Tulsa, Oklahoma 74147

Well total depth 3845 feet ^{124.96}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 234 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License#

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 13 Month: October Year: 92

Plugging proposal received from: Robert R. Price

Company: Robert R. Price Operating, Inc. Phone:

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.
Just pulled rods and tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 13, Month: October, Year: 92

Actual plugging report: 8 5/8" set @ 234' w/250 sx. cwc. 5 1/2" set @
3837' w/150 sx. Perf's 3654' - 3775'. P.B.T.D. 3810'. Shots @ 1920' -
1921'. Hole in Dakota. Squeezed 5 1/2" w/300 sx. cement blend
w/500# hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. 200#.
Squeezed 8 5/8" w/100 sx. cement blend to Max. P.S.I. 400#. Close in
P.S.I. 200#. Plug completed.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

NOV 9 1992

I did [X] / did not [] observe the plugging.

Carl Goodrow

DATE 11-23-92

ND

(agent)

INV. NO. 36858

Form CP-2/3