

4- 031777

10-13

34 R

15-065-01544-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ~~15~~ - ~~1956~~

SW NE NE /4 SEC. 32 , 09 S, 22 W
4290 feet from S section line
990 feet from E section line

Operator license# 6273 Lease Sturgeon well # 3

Operator: Robert R. Price Oper., Inc. County Graham

Address: Box 470442 Well total depth 3885 feet ^{126.26}
Tulsa, Oklahoma 74147 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 238 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 13 Month: October Year: 92

Plugging proposal received from: Robert R. Price

Company: Robert R. Price Operating, Inc. Phone: -

Were: Order 450 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to perf.
Just pulled rods and tubing.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:30P.M., Day: 13, Month: October, Year: 92

Actual plugging report: 8 5/8" set @ 238' w/250 sx. cwc. 5 1/2" set @
3883' w/150 sx. Perf's 3709' - 3796'. P.B.T.D. 3856'. Circ. cement from
1345' w/150 sx. cement at surface in 8 5/8". Squeezed 5 1/2" casing
w/370 sx. cement blend w/350# hulls mixed in to Max. P.S.I. 400#.
Close in P.S.I. 400#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

11/9/92
NOV 9 1992

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO
Bottom plug(in place):YES X ,CALC ,NO Dakota plug:YES X ,NO
Plugged through TUBING , CASING X . Elevation: GL.

I did[X] / did not[] observe the plugging. Carl Goodrow

DATE 11-23-92

INV. NO. 36859

(agent)