

*Call  
Munt  
7/14/08*

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 033-20871-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3-25-1993

Well Operator: ARES Energy, Ltd. KCC License #: 33770

Address: 303 West Wall Street, Suite 900 City: Midland

State: Texas Zip Code: 79701 Contact Phone: (432) 685 - 1960

Lease: Bluff Creek Well #: 5-15-OWWO Sec. 5 Twp. 34 S. R. 20  East  West

NW - SW - SE Spot Location / QQQQ County: Comanche

1,100 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2,500 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: Re-entry Dry

Conductor Casing Size: 20", 36# Set at: 60' Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8", 24# Set at: 675' Cemented with: 60/40 & Class "A" 225 & 100 Sacks

Production Casing Size: 4-1/2", 10.5# Set at: 5,412 Cemented with: Class "H" 223 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations: 5,348' - 5,358'

Elevation: 1,769' ( G.L. /  K.B.) T.D.: 5,412' PBDT: 5,394' Anhydrite Depth: 803'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP @ 5,300' & Dump 30' Cement on top. Cut off 4-1/2"

Casing @ +/- 4,000' & Pull. Spot 50 Sx Plug @ +/- 4,050'. Spot 50 Sx Plug @ 700'. Spot 10 Sx Plug @ 40'.

Is Well Log attached to this application as required?  Yes  No Is ACO-T filed?  Yes  No

If not explain why? Logs and reports associated with drilling and plugging the original Bluff Creek 5-15 Well were furnished to the KCC by Samuel Gary Jr. & Associates, Inc. in 1993.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Brian Ramey, Operations Manager Phone: (432) 685 - 1960

Address: 303 West Wall Street, Suite 900 City / State: Midland, Texas 79701

Plugging Contractor: Best Well Service, Inc. KCC License #: 32564

Address: P. O. Box 1244, Liberal, Kansas 67905-1244 Phone: (620) 624 - 9524

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-9-2008 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 10 2008  
CONSERVATION DIVISION  
WICHITA, KS

# ARES ENERGY LTD.

July 9, 2008

VIA FEDERAL EXPRESS

*maggie*  
~~Ms. Pam Thorne~~  
Kansas Corporation Commission  
130 South Market, Room 2078  
Wichita, Kansas 67202

RE : Bluff Creek 5-15 OWWO  
Comanche County, Kansas  
API: 15-033-20871-0001

Dear Ms. ~~Thorne~~: *maggie*

Pursuant to my telephone conversation with Jim Hemmen, enclosed please find the following:

- 1) CP-1 Well Plugging Application

We plan to have a rig from Best Well Service, Inc. available next week to plug the well.

If you have any questions or need any additional information, please contact me at ARES Energy, Ltd. at the telephone number shown on the letterhead.

Very truly yours,

ARES Energy, Ltd.

*Welda J. Bates*

Welda J. Bates  
Land Administrator

Enclosures

Cc: Steve Durrant, KCC, Dodge City, Kansas

Cc: Jim Hemmen, KCC, Wichita, Kansas

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 10 2008

CONSERVATION DIVISION  
WICHITA, KS



# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ARES ENERGY, LTD  
303 W WALL STE 900  
MIDLAND, TX 79701-5116

July 14, 2008

Re: BLUFF CREEK #5-15  
API 15-033-20871-00-01  
5-34S-20W, 1100 FSL 2500 FEL  
COMANCHE COUNTY, KANSAS


Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after January 10, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,



Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888