

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: BENJAMIN M. GILES  
Address: 532 SOUTH MARKET, WICHITA, KS 67202  
Phone: (316) 265-1992 Operator License #: 5446  
Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: DAVE WERTZ & MIKE WILSON (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
KANSAS CITY Depth to Top: 2545 Bottom: 2709 T.D. 3421  
HUNTON Depth to Top: 3419 Bottom: \_\_\_\_\_ T.D. 3421  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-173-20,029-00-01  
Lease Name: HALEY  
Well Number: 1 OWWO  
Spot Location (QQQQ): SE - NE - NE  
990 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 34 Twp. 25 S. R. 1  East  West  
County: SEDGWICK  
Date Well Completed: 09/27/07  
Plugging Commenced: 07/25/08  
Plugging Completed: 07/25/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KANSAS CITY	OIL & WATER	0	2215	5 1/2	2215	2164
HUNTON	OIL & WATER					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

WASHED DOWN TO TOP OF OLD PIPE AT 2215'. HOOKED ONTO OLD PIPE AND SET 2215' OF USED 5 1/2" CASING. COULD NOT GET PAST PATCH WITH BIT AND TUBING (IRON IN THE HOLE). DID NOT GET TO LOWER PLUG, SHOT 5 1/2" CASING OFF AT 2164' AND PULLED 2164' OF CASING. FILLED WITH MUD TO 250', RUN TUBING IN AND CEMENTED TO SURFACE WITH 115 SAX OF 60-40 POZ MIX. PULLED 2 7/8" TUBING. COPY OF CEMENT TICKET ATTACHED. COMPLETED PLUGGING ON 07/25/08.

Name of Plugging Contractor: COPELAND ACID & CEMENT License #: 3004 9998-1  
Address: BOX 438, HAYSVILLE, KS 67060

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 30 2008

Name of Party Responsible for Plugging Fees: BEN GILES  
State of Kansas County, Sedgwick, ss.

CONSERVATION DIVISION  
WICHITA, KS

Benjamin M. Giles (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God..

(Signature) Benjamin M. Giles  
(Address) 532 So Market Wichita ks 67202

SUBSCRIBED and SWORN TO before me this 30<sup>th</sup> day of July, 2008  
Tauri L. Raney My Commission Expires: 04/03/10  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



