

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation
Address: 100 S. Main, Suite 200, Wichita, KS 67202
Phone: (316) 262-3596 Operator License #: 9408
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/23/08 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 3384' Bottom: 3386' T.D. _____
Marmaton Depth to Top: 3392' Bottom: 3398' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-22782-00-00
Lease Name: Thomas "A"
Well Number: 2
Spot Location (QQQQ): W2 - NW - NE -
660' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 24S Twp. 8 S. R. 18 East West
County: Rooks
Date Well Completed: 1985
Plugging Commenced: 7/23/08
Plugging Completed: 7/23/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	261'	8-5/8"		
		surface	3402'	4-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Klima Well Serv run tbg to 1400'. Spot 60 sxs 60/40 Poz Mix 4% gel and 100# hulls. Pull tbg to 700' spot and circulate to surface w/ 60 sxs 60/40 Poz 4% gel 100# hulls. Squeeze 8 5/8 w/15 sxs, Squeeze to 250 # SI .Top off csg w/10 sxs .RDMO Pat W/KCC was in attendance. 7/23/08 To P&A

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Plugging Contractor: Klima Well Service, Inc. License #: 7023
Address: P.O. Box 386, Claflin, KS 67525
Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation

State of Sedgwick County, Kansas, ss.

Gary Sharp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Sharp
(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 24th day of July
Glenna E. Lowe My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pat