

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: T n T Engineering
Address: P. O. Box 187 Plainville, Ks
Phone: (785) 737-3736 Operator License #: 33699
Type of Well: oil Docket #: na
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/16/08 (Date)
by: Mr. Rich Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3381 Bottom: 3384 T.D. 3450
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - completed 2/18/40
Lease Name: Stein
Well Number: 3
Spot Location (QQQQ): C - n/2 - sw/4 - se/4
990 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 7 Twp. 11 S. R. 17 East West
County: Ellis
Date Well Completed: 2/18/40
Plugging Commenced: 7/17/08
Plugging Completed: 7/17/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	40	16"		0
		0	1120	10 - 3/4"		0
		0	3382	7"		0
		3292	3450	5" liner		0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran open end tubing to 3200' Pumped 75 sxs 60/40 poz w/ 300# hulls, cc, and 25 sxs of gel. Pull tubing out to 1650'. Pumps 60 sxs cement w/ 100# hulls.
Pull tubing to 1125' and pumped 225 sxs with circulation out 7" and 10-3/4" casing throughout stage until cement surfaced. Let cement stand while breaking out connections and top of casing with cement.

Name of Plugging Contractor: Allied Cementing License #: MA 99990
Address: 24 S Lincoln Russell, Ks


Name of Party Responsible for Plugging Fees: T n T Engineering
State of Texas County, Wichita, ss.

Randy Weigel (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Weigel
(Address) 2190 16rd Plainville, Ks.

SUBSCRIBED and SWORN TO before me this 22nd day of July, 2008
S.J. Stahl My Commission Expires: 03-05-2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



KCC Plot
RECEIVED
KANSAS CORPORATION COMMISSION
JUL 24 2008
CONSERVATION DIVISION
WICHITA, KS