

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 6-6-08 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Council Grove Depth to Top: 2798 Bottom: 2902 T.D. 3010'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-20364-00-00
Lease Name: Bentley A
Well Number: 2 KCC Pkt EP2/3
Spot Location (QQQQ): NW NW - SE - NW
1390 Feet from ☒ North / ☐ South Section Line
1340 Feet from ☐ East / ☒ West Section Line
Sec. 14 Twp. 34 S. R. 40 ☐ East ☒ West
County: Morton
Date Well Completed: 5-8-79 spud
Plugging Commenced: 6-10-08
Plugging Completed: 6-12-08

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	539	-
				4 1/2	3009	1033

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8 to fill in 4 1/2 @ 2400. Mixed 200 lb. hulls to 20 sx cmt.
plug from 2400 to 2200. Shot to pull 4 1/2. Ran 2 3/8 to 1033.
Circ. hole w/mud + hulls. Mixed 50 sx plug 1033 to 883
50 sx 570 to 420 10 sx 40 to 0 Capped 8 5/8 3ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Sevier, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED and SWORN TO before me this 21 day of July, 2008

RECEIVED
KANSAS CORPORATION COMMISSION

Anita Peterson
Notary Public

My Commission Expires: Oct. 1, 2009

JUL 23 2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS