

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Curt's Oil Operations  
Address: P.O. Box 8, Great Bend, KS 67530  
Phone: (620) 793-2540 Operator License #: 4871

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: N/A (Date)  
by: Bruce Basye (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 009-22-883 - 00-00  
Lease Name: Feltes  
Well Number: #1-A KCC PKT Per CP2/3  
Spot Location (QQQQ): W/2 - NE - NE - NWNE  
330 Feet from ☒ North / ☐ South Section Line  
330/365 Feet from ☒ East / ☐ West Section Line  
Sec. 34 Twp. 16 S. R. 12 ☐ East ☒ West  
County: Barton  
Date Well Completed: 9/3/1982  
Plugging Commenced: 6/26/2008  
Plugging Completed: 6/26/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	250'	8-5/8"	250'	0'
	Production	0'	3359'	4-1/2"	3359'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate well @ 1500' - 800' - 250'. Run tubing to 3000'. Mix 50 sks of 60/40 poz w/ 4% gel w/ 100# hulls @ 3000'. Pull tubing to 2700'. Mix 7 sks gel. Pull tubing to 1600'. Mix 130 sks w/ 300# hulls. Circulated cement to surface. Pull tubing out and broke off well. Swedge in 4-1/2". Mix 40 sks. Circulated out annulus. Shut annulus in. Squeezed to 250 PSI. Rigged down.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901  
Address: 1822 24th Street, Great Bend, KS 67530

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 23 2008


Name of Party Responsible for Plugging Fees: Curt's Oil Operations

State of Kansas County, Barton, ss.

CONSERVATION DIVISION  
WICHITA, KS

Curtis Hitschmann

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) Curtis L. Hitschmann  
(Address) P.O. Box 8, Great Bend, KS 67530

SUBSCRIBED and SWORN to before me this 21<sup>st</sup> day of July, 2008  
Vicki L. Sheets My Commission Expires: 10-7-08  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT