

JUL 30 2008

CONSERVATION DIVISION  
WICHITA, KS

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 025-21457-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 07/25/08

Well Operator: Diversified Operating Corporation KCC License #: 33060

Address: 15000 West 6th Ave. Suite 102 (Owner / Company Name) City: Golden (Operator's)

State: Colorado Zip Code: 80401 Contact Phone: ( 303 ) 384 - 9611

Lease: Hardin KCC PPT Well #: 9A-3-5 Sec. 9 Twp. 32 S. R. 21  East  West

SW NW - NE - NW Spot Location / QQQQ County: Clark

365 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1455 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 20" Set at: 100 Cemented with: Grout Sacks

Surface Casing Size: 13 3/8 Set at: 457 Cemented with: 375 Sacks

Production Casing Size: 4 1/2 Set at: 5301 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5220-38

Elevation: 1983 ( G.L. /  K.B.) T.D.: 6500 P.B.T.D.: 5277 Anhydrite Depth: \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set CIBP at 5200' Dump 2 sxs cement on it. Recover as much 4 1/2 inch casing as possible. Cement top 4750'. TIH with tubing. Set 50 sack plug at 1000'. POOH to 480' Set 50 sack plug. POOH to 300' Set 50 sack plug. POOH to 60' Set 20 sack plug. Use 60-40 Pozmix with 4% gel. KCC to be on location for open hole plugs.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Completion failed in Morrow. Had verbal permission to start plugging. Will send logs with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Jason Walker

Phone: ( 620 ) 786- - 5600

Address: \_\_\_\_\_ City / State: Great Bend, Kansas

Plugging Contractor: Plains KCC License #: 33645

Address: PO Box 346 Ness City, KS 67560 (Company Name) Phone: ( 785 ) 798 - 3995 (Contractor's)

Proposed Date and Hour of Plugging (if known?): Starting July 28th, 2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/25/08 Authorized Operator / Agent: Bill Walker (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Dist 1*  
*PPT*



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

DIVERSIFIED OPERATING CORP.  
15000 W 6TH AVE STE 102  
GOLDEN, CO 80401-5047

August 01, 2008

Re: HARDIN #9A-3-5  
API 15-025-21457-00-00  
9-32S-21W, 392 FNL 1328 FWL  
CLARK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after January 28, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely,

Steve Bond  
Production Department Supervisor