

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 075-10023 - 00 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-18-62

Well Operator: Linn Operating, Inc. KCC License #: 33999
(Owner / Company Name) (Operator's)

Address: 600 Travis, Suite 7000 City: Houston

State: TX Zip Code: 77002 Contact Phone: (405) 241 - 2223

Lease: HCU Well #: 3311 Sec. 33 Twp. 21 S. R. 41 East West

- C - NW - SE Spot Location / QQQQ County: Hamilton

1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NA Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 205' Cemented with: 150 Sacks

Production Casing Size: 4-1/2" Set at: 2810' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2771' - 2773'

Elevation: 3648 (G.L. / K.B.) T.D.: 2810 PBTD: 2809 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Run CIBP & Set @ 2721'. Dump 20' CMT on BP. Determine F.P. on 4-1/2".

Cut & pull Csg. Run Tbg to 305'. Pump 100 SX Cmt, tag. Pull Tbg to 60'. Pump 20 SX Cmt to surface. Dig out WH, cut off BGL. Weld on

ID plate.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Darrin Valliquette

Phone: (405) 341 - 1913

Address: PO Box 30660 City / State: Edmond, OK 73003

Plugging Contractor: Bronco KCC License #: 7407
(Company Name) (Contractor's)

Address: 16217 N. May Ave, Edmond, OK 73013 Phone: (405) 261 - 0978

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/29/08 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2026, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION
WICHITA, KS

Dist 1
PKT



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

LINN OPERATING, INC.
600 TRAVIS STE 7000
HOUSTON, TX 77002-3018

August 05, 2008

Re: HCU #3311
API 15-075-10023-00-00
33-21S-41W, 1980 FSL 1980 FEL
HAMILTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 1, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888