

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

Form CP-1

September 2003

Form must be Typed

Form must be Signed

All blanks must be Filled

WELL PLUGGING APPLICATION

AUG 07 2008

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15- 187-20784-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 9/15/1995

Well Operator: Presco Western, LLC KCC License #: 32309

(Owner/Company Name)

(Operator's)

Address: 5665 Flatiron Parkway City: Boulder

State: CO Zip Code: 80301 Contact Phone: 303 305-1163

Lease: Yardley Frederick *KCC PRT per operator* Well #: 1-25 Sec. 25 Twp. 29 R. 40 East West

Spot Location/QQQQ County Stanton

990 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

2,300 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 1,716' Cemented with: 735 Sacks

Production Casing Size: 5-1/2" Set at: 5,765' Cemented with: 700 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 5,620-5,630', CIBP @ 4,950', 4,000', 2,880'

Elevation: 3,230 (G.L. K.B.) T.D. 5,778' PBDT 5,720' Anhydrite Depth 1,691'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 1st plug: Spot @ 4,000' 5 SKS OMT, 2nd plug:

Spot @ 2,880' 5 SKS OMT, 3rd plug: Spot 100' OMT across 8-5/8" csg shoe @ 1,716'. 4th plug: Spot 700'

OMT in 5-1/2" csg and 5-1/2 x 8-5/8" annulus.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Comment: Verbal agreement btw Russ Shucker (Presco Western, LLC) & Steve Pfeifer

(District 1) on 7/31/2008

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Steve Ridenour Phone: 620 655-3459

Address: 303 S. Stubbs Rd. City/State Ulysses/KS 67880

Plugging Contractor Presco Western, LLC (Basic Energy) *Halliburton services* KCC License # 32309 5287 99997
(Company Name) (Contractor's)

Address 5665 Flatiron Parkway, Boulder, CO 80301 Phone: 303 305-1163

Proposed Date and Hour of Plugging (if known?): 8/14/2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/6/2008 Authorized Operator / Agent: Keli Kowalski

(Signature)

Keli Kowalski

KCC Per License

District 1

PRT



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

PRESCO WESTERN LLC
5665 FLATIRON PKWY
BOULDER, CO 80301

August 11, 2008

Re: FREDERICK YARDLEY #1-25
API 15-187-20784-00-00
25-29S-40W, 990 FSL 2300 FWL
STANTON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after February 7, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888