

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

RECEIVED

KANSAS CORPORATION COMMISSION September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

AUG 07 2008

Please TYPE Form and File ONE Copy

CONSERVATION DIVISION
WICHITA, KS

API # 15- 187-20422-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 4/18/1994

Well Operator: Presco Western, LLC KCC License #: 32309

(Owner/Company Name) City: Boulder (Operator's)

Address: 5665 Flatiron Parkway

State: CO Zip Code: 80301 Contact Phone: 303 305-1163

Lease: Esser Well #: 2-16 Sec. 16 Twp. 29 R. 39 East West

Spot Location/QQQQ County Stanton

1004 980 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

4331 980 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 1,726' Cemented with: 450 Sacks

Production Casing Size: 5-1/2" Set at: 5,831' Cemented with: 465 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 5,467 - 5,482 & 5,492 - 5,516, CIBP @ 5,400 & 2,850

Elevation: 3,222 (G.L. K.B.) T.D. 5,841' PBDT _____ Anhydrite Depth _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 1st plug: spotted @ 5,400' w/ 5 SKS OMT
2nd plug: spotted @ 2,850' w/ 5 SKS OMT, 3rd plug: spotted @ 1,726' in 5-1/2" csg, across 8-5/8" csg shoe
w/ 50 SKS OMT, 4th plug: perf 5-1/2" csg @ 700', inject 100SKS OMT in 5-1/2 x 8-5/8 annulus to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Comment: Verbal agreement 1st made btw Steve Durant (Dist.1) and Randy Verret (Presco
Western, LLC) on 7/3/2008, then revised on 7/7/2008

Plugging of this Well will be done in accordance with K.S.A. 55-101 et seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Steve Ridenour Phone: 620 655-3459

Address: 303 S. Stubbs Rd. City/State Ulysses, KS 67880

Plugging Contractor Presco Western LLC (Basic Energy) KCC License # 32309 34069
(Company Name) (Contractor's)

Address 5665 Flatiron Parkway, Boulder, CO 80301 Phone: 303 305-1163

Proposed Date and Hour of Plugging (if known?): 7/9/2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/6/2008 Authorized Operator / Agent: Keli Kowalski
(Signature)

Keli Kowalski

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well plugged - KCC-PKT

Dist 1
PKT